



# ROLAIR<sup>®</sup> COMPRESSORS

S Y S T E M S

606 South Lake Street > P.O.Box 346 > Hustisford, WI 53034-0346 > 920.349.3281 > fax 920.349.3691 > www.rolair.com

**Super Quiet!  
Only 8 Amps**



## Model JC10

**Direct Drive – Oilless**

- **1 HP** 1725 RPM, Auto Reset
- **2.35 CFM** Delivered at **90 PSI, 5.3** Displaced
- \*Runs Approximately**
  - 1-2 Roofing Guns
  - 2-3 Trim/Finish Guns

**Low Speed  
Low Noise**



## Model VT20TB

**Direct Drive – Splash Lubricated**

- **2 HP** 1700 RPM, Manual Reset
- **4.2 CFM** Delivered at **90 PSI, 5.5** Displaced
- \*Runs Approximately**
  - 1-2 Framing Guns
  - 1-2 Roofing Guns
  - 3-5 Trim/Finish Guns



## Model FC1500HBP2

**Direct Drive – Splash Lubricated**

- **1.5 HP** 3400 RPM, Manual Reset
- **4.0 CFM** Delivered at **90 PSI, 7.8** Displaced
- \*Runs Approximately**
  - 1 Framing Gun
  - 1-2 Roofing Guns
  - 1-3 Trim/Finish Guns



## Model VT25BIG

**Direct Drive – Splash Lubricated**

- **2.5 HP** 3400 RPM, Manual Reset
- **6.5 CFM** Delivered at **90 PSI, 9.3** Displaced
- \*Runs Approximately**
  - 2-3 Framing Guns
  - 3-4 Roofing Guns
  - 6-8 Trim/Finish Guns



## Model FC2002

**Direct Drive – Splash Lubricated**

- **2 HP** 3400 RPM, Manual Reset
- **4.1 CFM** Delivered at **90 PSI, 8.7** Displaced
- \*Runs Approximately**
  - 1-2 Framing Guns
  - 1-2 Roofing Guns • 3-5 Trim/Finish Guns

**Large  
24 Gallon  
Dolly Tank**



## Model FC250090L

**Direct Drive – Splash Lubricated**

- **2 HP** 3400 RPM, Manual Reset
- **5.1 CFM** Delivered at **90 PSI, 10.1** Displaced
- \*Runs Approximately**
  - 1-2 Framing Guns
  - 2-3 Roofing Guns
  - 4-6 Trim/Finish Guns



## Model D2002HPV5

**Direct Drive – Splash Lubricated**

- **2 HP** 3400 RPM, Manual Reset
- **4.1 CFM** Delivered at **90 PSI, 8.7** Displaced
- \*Runs Approximately**
  - 1-2 Framing Guns
  - 1-2 Roofing Guns
  - 3-5 Trim/Finish Guns



## Model GD4000PV5H

**Gas Direct Drive**

- **118 cc (GX120)** Honda Engine, Splash Lubricated
- **4.6 CFM** Delivered at **90 PSI, 8.3** Displaced
- \*Runs Approximately**
  - 1-2 Framing Guns
  - 2-3 Roofing Guns
  - 4-6 Trim/Finish Guns

**\*Number of tools is dependent on the efficiency of the contractor's pneumatic system.**